OFFICE OF THE SUPERINTENDENT, POWER AND LIGHTING, MYSORE.

Notification dated the 25th March 1937.

Sealed tenders, in triplicate, will be received at the Office of the Superintendent, Power and Lighting, Mysore. Tenders should be superscribed with the name of the work given below :—

2. The plans may be seen in the office of the undersigned at all working hours.

3. The tenders should be drawn up in conformity with the specifications furnished below writing out the rates at which the different items of work will be executed, in figures as well as in words, failing which the tenders will be disqualified.

4. The undersigned reserves the right to reject the tenders without assigning any reason therefor.

5. The successful tenderer will be required to deposit with the undersigned an earnest money of Rs. 200 (Rupees two hundred) and execute an agreement within 3 days from the date of receipt of intimation as to the acceptance of tender, failing which the tender will be disposed of otherwise.

6. Materials to be used on the work should either best quality English or American Manufacture and conform to the specifications. The work should be executed strictly in accordance with the wiring rules of this Department as well as that of the Institution of Electrical Engineers. Mention should also be made of the catalogue numbers of the materials offered.

7. No items other than those noted in the statement should be included in the tender as the items include provision for masonry repairs, painting, etc.

8. The successful tenderer should carry out any changes that might be suggested during the progress of the work, with regard to the location of the fixtures, switch-points, etc., without extra cost, if the estimate is not materially affected by such a deviation.

9. *Name of work.*—Installing Electric Lights to the Ground and First Floors of the Central Block of Law Courts Buildings, Mysore.

10. Last date and time of receiving the tenders is 10th April 1937 at 3 P.M.

11. Time and date for opening the tenders in public is 4-30 P.M., on 10th April 1937.

12. The time allowed for the completion of the work is four weeks from the date of acceptance of the tender, failing which a penalty of annas two for each day's delay over and above the stipulated time will be enforced.

13. *Details of work:*—

PART I—(Exterior Works.)

	Quantity.
(1) Supplying and laying No. 4 B. & S. twin-conductor, paper insulated, lead covered, double steel tape armoured, jute served, underground cable in a trench 3′ deep, surrounding the same with 3″ of fine sand, enclosing the ends in pole and in-door type junction boxes filled with insulating compound, and the exposed portion of the cable running along the pole in 25′ of 2″ glvd. pipe, using necessary clamps, No. 4 B. & S. insulated wire, 2,500 Meg.-Ohm. grade and accessories	320 ft.
(2) Running mains in 1″ W.I. pipe, using No. 4 B. & S. 2,500 Meg-Ohm. grade insulated wire and accessories	65 ft.
(3) Earthing	*Item.*

PART II—(Ground Floor).

(1) Supplying, fixing and wiring teakwood board 30″×21″×1″ with battens and rear board, equipping it with a 30 amp. D.P. iron-clad switch with fuses. One pair of 30 amp. Senior Home Office type fuse units, one 8-way D.P.H.O. Pattern 10 amp. per way distribution board, with 10 amp. circuit switches with bakelite cover, using No. 4, 8 and 12 B. & S. 2,500 Meg-Ohm grade insulated wires and accessories	1
(2) Running circuit mains in T. W. 2″×1″ 2-way casing treated with 2 coats of Shellac varnish, using No. 12 B. & S. 2,500 Meg-Ohm. grade insulated wire and accessories. (to feed Northern and Southern units, central record room, and additional Sub-Judge's Office)	300 ft.
(3) Supplying, fixing and wiring in teakwood 2-way 2″×1″ casing treated with 2 coats of Shellac varnish for drop lights, complete with 2-plate bakelite ceiling rose, flexible cord, B.C.C.G. reinforced bakelite lamp holder, 5-amp. bakelite control switch, using No. 12 and 14 B. & S. 2,500 Meg-Ohm. grade insulated wires for mains and taps, respectively, and accessories	8
(4) Do do for 'Bharat' Ceiling Fans 60 cycles, 230 volts, 3 blades, 56″ sweep, complete with canopy, down rod, suspension clamp, 5 point variable speed regulator, fitted underneath it a Trojan Lighting unit, complete with B.C. lamp holder, canopy, 12″ glass ware, etc., using 3 plate bakelite ceiling rose, flexible cord, 5 amp. bakelite control switch, etc., as above	

		Quantity.
(5)	Supplying, fixing and wiring for "Bharat" Ceiling Fans, 60 cycles, 230 volts, 3 blades, 56" sweep, complete with canopy, down rod, suspension clamp, 5 point variable speed regulator, etc., using 2 plate bakelite ceiling rose, No. 12 and 14 B. & S. 2,500 Meg-Ohm. grade insulated wires, for mains and taps, respectively, and accessories	1
(6)	Do do in T. W. 2"×1" 2-way casing treated with 2 coats of Shellac varnish for Trojan Lighting units, complete with canopy, B.C. lamp holder, suspension chain, 12" glass ware, flexible cord, etc., using 2 plate bakelite ceiling rose, 5 amp. bakelite control switch, No. 12 and 14 B. & S. 2,500 Meg-Ohm. grade insulated wires, for mains and taps, respectively, and accessories	1
(7)	Do do for Trojan lighting units, with 9" glass ware, as per specification above..	4
(8)	Do do for $\frac{5}{8}$" brass pendants, complete with stout brass ceiling plate, B.C. lamp holder (all nickel plated) 2 to 3 feet long, using 5 amp. bakelite control switch, etc., as per specification above ..	6
(9)	Do do for combined wall plug and switch bakelite with nipple, complete, as per specification above	6
(10)	Supplying and fixing globes opal 6"×5$\frac{1}{4}$"×3$\frac{1}{4}$", with gallary	8
(11)	Do do Coolican Reflectors 9"	6
(12)	Do do Lamps, gas-filled, 230 volts, B.C. 150 watts. ..	7
(13)	Do do do 100 watts.	4
(14)	Do do do 60 ,, ...	14
(15)	Earthing	*Item.*

PART III—(First Floor).

(1)	Supplying and running sub-mains in T. W. 2"×1" 2-way casing treated with 2 coats of Shellac varnish using No. 8 B. & S. 2,500 Meg-Ohm. grade insulated wire and accessories	25 ft.
(2)	Supplying, fixing and wiring T. W. board 24"×18"×1" with battens and rear board, equipping it with a 30 amp. D.P. iron-clad switch with fuses, one 4-way D.P.H.O. pattern 10 amp. per way distribution board with 10 amp. circuit switches, with bakelite cover, using No. 8 and 12 B. & S. 2,500 Meg.Ohm. grade insulated wires and accessories.. ..	1
(3)	Do do in T. W. 2"×1" 2-way casing treated with 2 coats of Shellac varnish for drop lights, complete with 2 plate bakelite ceiling rose, flexible cord, B.C.C.G. reinforced bakelite lamp holder, 5 amp. bakelite control switch, etc., using No. 12 and 14 B. & S. 2,500-Meg-Ohm. grade insulated wires, for mains and taps, respectively, and accessories	10
(4)	Do do for $\frac{5}{8}$" brass pendants, complete with stout brass ceiling plate, B.C. Lamp holder (all nickel plated) 2 to 3 ft. long, using 5 amp. bakelite control switch, etc., as per specification above ..	7
(5)	Supplying, fixing and wiring for Trojan lighting units, complete with canopy, suspension chain, B.C. lamp holder, 9" glass ware, using 2 plate bakelite ceiling rose, 5 amp. bakelite control switch, etc., as per specification above	1
(6)	Do do for 'Bharat' ceiling fans 60 cycles, 230 volts, 3 blades, 56" sweep, complete with canopy, down rod, suspension clamp, 5 point variable speed regulator, etc., fitted underneath it, with a Trojan lighting unit, complete with canopy, B.C. lamp holder, 12" glass ware, etc., using 3 plate bakelite ceiling rose, flexible cord, 5 amp. bakelite control switch, etc., as per specification above	4
(7)	Do do for ceiling fans (available), complete, as per specification above	2
(8)	Do do for combined wall plug and switch bakelite with nipple, complete, as per specification above	3
(9)	Supplying and fixing Coolican Reflectors, 9"	7
(10)	Do do Globes opal 6"×5$\frac{1}{4}$"×3$\frac{1}{4}$" with gallary	8
(11)	Do do lamps gas-filled, B.C. 230 volts, 150 watts	6
(12)	Do do do 100 watts.	1
(13)	Do do do 60 ,, ...	17
(14)	Earthing	*Item.*

PART IV—(Additions and alterations to the Central Record Room). *Quantity.*

(1) Supplying, fixing and wiring a teak wood board 12″×12″×1″, with battens and rear board, equipping it with a 15 amp. D.P. iron-clad switch with fuses, using No. 12 B. & S. 2,500 Meg-Ohm. grade insulated wires and accessories 1

(2) Re-arranging the existing lights, providing independent control switches, using available materials and necessary accessories 6

(3) Supplying B.C. batten lamp holders bakelite and wiring in teakwood casing with independent control switches, using available materials and necessary accessories 6

Abstract.

Part I	..	Rs.
Part II	..	Rs.
Part III	..	Rs.
Part IV	..	Rs.
Total		Rs.

M. HAYATH,
Superintendent.

OFFICE OF THE EXCISE COMMISSIONER IN MYSORE, BANGALORE.

Notice No. A1-1320—36, *dated 25th March* 1937.

The Sales of Excise and Opium Privileges of Koppa Taluk for the year 1937-38 will be held on Friday the 23rd April 1937, instead of Saturday the 24th April 1937, as announced in this office Notification No. A1-1320—36, dated 3rd March 1937 relating to the Sales of Excise and Opium Privileges for the year 1937-38, published in the *Mysore Gazette*, dated 11th March 1937.

S. ABDUL WAJID,
Excise Commissioner.